



SportsPlay 301-146 10' Merry-Go-Round Specifications

Specifications:

- Consists of 6 plastisol coated deck sections manufactured from 12 ga. steel.
- Post is 2.5" solid steel post 48" long with rebar reinforcing, set with a 36" wide x 36" deep hole. Will take approximately 1280 lbs of concrete (16- 80 lb bags). Concrete must cure 7 days before installation of merry go round.
- □ Mechanical governor to limit speed
- □ 1.5" solid steel ball bearing
- □ Bolt together assembly, which allows for easy replacement of any damaged parts.
- □ 6 Handrails are manufactured with 1 5/8" O.D. pipe welded together for easy installation.